

**SCOPE OF WORK MAY INCLUDE:**

- \* Stabilize roadway using Asphalt Emulsion Stabilizer.
- \* Stabilize Roadway using Lime Kiln Dust.
- \* Excavate existing roadway and install 10" of new Limestone Aggregate.
- \* Place 2 Course Surface Treatment.
- \* Replace existing drainage culverts if needed.
- \* Install signage and pavement markings as required.

**PRECINCT #1**

ROAD NAME	LENGT WIDTH		SQ. YARDS
	H (FT)	(FT)	
TIEMANN RD	5,348	22	13,073
WOELKE RD	15,500	22	37,889
SCHUMANN RD (DITCH)			
			<b>50,962</b>

**PRECINCT #2**

ROAD NAME	LENGT WIDTH		SQ. YARDS
	H (FT)	(FT)	
HUBER RD	7,603	22	18,585
OLD SEGUIN RD	6,072	24	16,192
GLENEWINKLE (DITCH)			
			<b>34,777</b>

**PRECINCT #3**

ROAD NAME	LENGT WIDTH		SQ. YARDS
	H (FT)	(FT)	

**PRECINCT #4**

ROAD NAME	LENGT WIDTH		SQ. YARDS
	H (FT)	(FT)	
SINGLE OAK RD	10,769	22	26,324
HOLMAN RD	1,362	22	3,329
			<b>29,654</b>

**\*\*Pending Inter-Local Agreements.**

**TOTAL SQ. YARDS = 115,392**

**Low water crossings:**

- Pieper Rd
- Barbarossa Rd
- Link Rd
- Lakecreek Dr