

PROPOSED 2019-2020 CONSTRUCTION SCHEDULE

SCOPE OF WORK MAY INCLUDE:

- *Stabilize roadway using Asphalt Emulsion Stabilizer.
- *Excavate existing roadway and install 10" of new Limestone Aggregate.
- *Place 2 course surface treatment.
- *Replace existing drainage culverts if needed.
- *Install signage and pavement markings as required.

PRECINCT #1

ROAD NAME	LENGTH (FT)	WIDTH (FT)	SQ. YARDS
Old Seguin-Luling Rd	22,750	22	55,611

PRECINCT #2

ROAD NAME	LENGTH (FT)	WIDTH (FT)	SQ. YARDS
Barbarossa Rd	8,496	22	20,768

PRECINCT #3

ROAD NAME	LENGTH (FT)	WIDTH (FT)	SQ. YARDS
None			

PRECINCT #4

ROAD NAME	LENGTH (FT)	WIDTH (FT)	SQ. YARDS
Jakes Colony Rd	15,010	22	36,691

TOTAL SQ. YARDS =**113,070**

Replace 1 failing low water crossing on Redwood Rd.

Upgrade 4 LWC on Old Seguin-Luling Rd

SPECIAL PROJECTS

SCHEDULE FOR 2020

1. Seal coat Sheriff Office Parking Lot Expansion and Impound Yard
 - a. 5800 Square Yards
 - b. Approximate Cost to Project: \$12,540

2. Remove and replace Handicap Parking Spaces at Justice Center
 - a. 25' x 20' in area in size
 - b. Approximate Cost to Project: \$1,450

3. *Marlow Ln –
 - a. 6,111 Square Yards
 - b. Reconstruct roadway to bring to current county standards.
 - c. Approximate Cost to Project: \$52,048

*Pending Road District